April 17th, 2015

Addendum No.1
Exterior Painting-Madera High School
Bid No. 041515-5

NOTICE TO ALL VENDORS:

This Addendum is attached to and made part of the above entitled specification for Madera Unified School District with a BID due date of April 22nd, 2015 by 12:00 p.m.

All Changes and/or clarifications will appear in bold type and deletions will be struck out within a sentence.

This Site will be a complete paint project:
Bid Bond-Due to the size and scope of project a Bid Bond is required - See Attached Form to Submit with Bid.

In the event that lead is found-report it immediately to MUSD- The District will have it abated
- **Do Not paint over murals**
- **Paint Flag polls**
- **Do not paint brick**
- **Paint all Stucco-patch where needed**
- **All doors and windows inside and out-including upper windows-repaint glass (where applicable)**
- **Paint all metal sash on windows-glazing (if needed)**
- **Art Building-no windows**
- **Paint shed behind cafeteria**
- **Engineering building-wood only on cover-no tin roof**
- **Cafeteria-do not paint exposed aggregate**
- **Remove and replace all signs**
- **Paint all hand rails**
- **Do not paint exposed aggregate**
- **All screens – removal and replace by contractor**
- **Paint frame on metal screens**
- **District responsible for dry rot**
- **Paint breeze ways**
- **Paint all metal trim**
- **All C-Trains**
- **All portables, handrails, ramps with Non-skid and paint in between**
- **"The Shed" weight room-paint entire building**
- **No pool fencing-paint back side of pool building and the trim**
- **Humanities Building-paint ducting for AC units**
- **Paint top of corrugated roof all canopy's(pressure wash prior to painting)**
- **Paint all downspouts**
- **No benches**
- **All rollup doors**