



ADDENDUM NO. 1

5/5/2023

PROJECT:	Berenda Elementary School Bud Loading Zone	OWNER:	Madera Unified School District 1902 Howard Road Madera, Ca 93637
ENGINEER:	Blair, Church & Flynn Attention: Lane Bader Kyle Lawson	BID NO:	042023
		BCF PROJECT NO.	221-0294

It will be the responsibility of the General Contractor to submit the information contained in this addendum to all its subcontractors and suppliers. Acknowledge receipt of this Addendum in the space provided on the Bid Form. Failure to do so may subject Bidder to disqualification. The following additions, deletions, and revisions to the Drawings and Project Manual are hereby made and do become a part of these Contract Documents.

TABLE OF CONTENTS

CHANGES TO BIDDING AND CONTRACT REQUIREMENTS

AD1-BR1: Bid Questions

ATTACHMENTS

None.

Blair, Church & Flynn Consulting Engineers

451 Clovis Avenue, Suite 200

Clovis, CA 93612

(559) 326-1400 FAX (559) 326-1500

CHANGES TO BIDDING AND CONTRACT REQUIREMENTS

AD1-BR1: Bid Questions

Q1: What manufacturer, type, and AIC rating is the existing MSB?

A1: Assume short circuit rating of 65KAIC or field investigate actual switchboard manufacturer and AIC Rating.

Q2: Other than note 5 on the electrical site plan, E201, is there any work with the solar canopy on this project

A2: No, all solar canopy work is self-contained

Q3: Are there any specs available for the electrical on this project

A3: All electrical work shall conform with the 2022 California Electrical Code, CEC, and the General Electrical Notes

Q4: Regarding the connection to the MSB, are any pull boxes required? If so, what size?

A4: Assume to rise up at the existing MSB and "LB" into the switchboard distribution section