

1902 Howard Road, Madera, CA 93637 559.675.4500 Fax: 559.675.1186 www.madera.k12.ca.us

February 16, 2024

Addendum No. 1 Bid No.020624-Roofing Projects at Multiple Sites

#### **NOTICE TO ALL VENDORS:**

This addendum is attached to and made a part of the above-entitled specifications for Madera Unified School District for Bid No.020624-Roofing Projects at Multiple Sites with a bid turn in date of February 27, 2024@ 10:00:00 a.m. (see updated timelines)

All changes and/or clarifications will appear in bold type and deletions will be struck out within a sentence.

# **Updated timelines:**

Pre-qualification packets due February 22, 2024 @ 10:00:00 am Pre-qualified vendors-posted February 28, 2024 @ 10:00:00 am Bid Turn In – March 6, 2024 @ 10:00:00 am.

See Attached:
Questions/clarifications

Signature:			
Date:			



# MADERA UNIFIED SCHOOL DISTRICT

Attachment to Addendum No.1 Bid No.020624

#### **Bid Section 1:**

- Change MLK Section 01 64 00 OFCI, Part 2, B, 8 to note the new roof panel width is to be 12" and not 18".
- Change MLK Section 07 41 00 Metal Roof Panels, Part 2, 2.2, B, 1, a to read 12" panel width and not 18". Change any and all references through the bid package from 18" to 12" panel width.
- Add to Nishimoto Section 01 11 00 Summary of Work, 1.3, D, Clean all gutters, seal all gutter laps with urethane sealant at all buildings.
- Add to Nishimoto Section 01 11 00 Summary of Work, 1.3, D, Remove all rivets from the ridge cap and install new butyl sealant between the laps, install new rivets and properly secure the ridge cap.

## **Bid Section 2:**

- Add to Chavez Section 01 11 00 Summary of Work, 1.3, D, Clean all gutters, seal all gutter laps with urethane sealant at all buildings.
- Add to Chavez Section 01 11 00 Summary of Work, 1.3, D, Remove all rivets from the ridge cap and install new butyl sealant between the laps, install new rivets and properly secure the ridge cap.

### **Bid Section 3:**

- Add to Nishimoto Section 01 11 00 Summary of Work, 1.3, D, Clean all gutters, seal all gutter laps with urethane sealant at all buildings.
- Add to Nishimoto Section 01 11 00 Summary of Work, 1.3, D, Remove all
  rivets from the ridge cap and install new butyl sealant between the laps,
  install new rivets and properly secure the ridge cap.

#### **Bid Section 4:**

- Add to Maintenance Shop Section 01 11 00 Summary of Work, 1.3, D, Install two existing leader heads back to the building at the small front roof sections.
   Install a new pre-finished sheet metal downspout from the leader box to the ground at both locations.
- Add to Maintenance shop Section 01 11 00, 07 22 00, & 07 55 00; Install one layer of 2" polyiso insulation board over the entire field of the roof. Both the Iso & Woodfiber layer can be attached with one common fastener per the proper fastening pattern as specified. Install a minimum of one 2"x4" nailer at the eve

# MADERA UNIFIED SCHOOL DISTRICT

edge and securely fasten to the structure. Install taper insulation board at the eve edge from the nailer height to the finished insulation height for proper drainage.