



# Madera Unified School District

1902 Howard Road, Madera, CA 93637  
559.675.4500  
Fax: 559.675.1186  
[www.madera.k12.ca.us](http://www.madera.k12.ca.us)

May 9, 2024

Addendum No.1-Bid No. 041824-Scoreboard Replacements at MHS Baseball and MSHS V. Softball

**NOTICE TO ALL VENDORS:**

This addendum is attached to and made a part of the above-entitled specifications for Madera Unified School District Bid No. 041824-Scoreboard Replacements at MHS Baseball and MSHS V. Softball, with a Bid Turn in date of May 16, 2024 @ 2:00:00 pm

All changes and/or clarifications will appear in bold type and deletions will be struck out within a sentence.

See attached.

Signature: \_\_\_\_\_

Date: \_\_\_\_\_

Terrie Lila  
Superintendent

Board of Trustees  
Lucy Salazar, President

Ruben Mendoza, Clerk  
Nadeem Ahmad

Israel Cortes  
Gladys A. Diebert

Joetta Fleak  
Ray G. Seibert

**MADERA UNIFIED SCHOOL DISTRICT BID NO. 041824****PRE-BID REQUEST FOR INFORMATION LOG**

<b>Prebid RFI</b>	<b>Question</b>	<b>Response</b>
1	Softball Scoreboard Drawings page SBO.1 sheet index identifies a three (3) column structure, but the drawing on sheet SBO.1, SB2.2 and SB5.2 show a two (2) column structure. Please clarify if two or three column structure is needed.	DSA # 02-122089: Sheet Index on sheet SB0.1 should direct contractor to sheet "SB2.2 TWO COLUMN CAISSON - BOLTED" not sheet "SB3.2 THREE COLUMN CAISSON - BOLTED."
2	Is Madera Unified supplying the scoreboards?	Yes, scoreboards have already been purchased.
3	Is Nevco mounting the scoreboards to the columns?	Yes, NEVCO is responsible for mounting the scoreboards to the contractor erected columns.
4	Is the truss option being utilized?	No, the truss option is not being utilized.
5	What is the bid allowance to be used for?	Owner requested changes. The district will retain control of the allowance at all times. Any unused sum will revert back to the district via a deductive change order.
6	Will the columns need to be painted or galvanized?	Galvanized
7	What is the projected start and end date for the project duration?	NTP June 11, Completion by August 5, 2024.
8	Is there an option to reinstall the new scoreboards to a different location and demo the existing footing 1' below grade?	Probably, but this is dependent on underground utility locations. Contractor should assume that the new scoreboards will go back at the same location as the existing scoreboards.
9	Final electrical connection to scoreboard by who?	NEVCO will make the final electrical connection. The contractor is responsible to bring power to the column with a proper shut-off switch as designated in the drawings.
10	Will the netting supports be needed as shown on sheet SB5.2?	Netting supports will not be needed.