



Madera Unified School District

1902 Howard Road, Madera, CA 93637
559.675.4500
Fax: 559.675.1186
www.madera.k12.ca.us

October 21, 2024

Addendum No. 1 Bid No.102124-MSHS Football Scoreboard Replacement Project

NOTICE TO ALL VENDORS:

This addendum is attached to and made a part of the above-entitled specifications for Madera Unified School District for Bid No. 102124-MSHS Football Scoreboard Replacement Project, with a Bid Turn in date of November 19, 2024 @ 10:00:00 am

All changes and/or clarifications will appear in bold type and deletions will be struck out within a sentence.

Clarification:

See Attached

Signature: _____

Date: _____

Todd Lile
Superintendent

Board of Trustees
Lucy Salazar, President

Ruben Mendoza, Clerk
Nadeem Ahmad

Israel Cortes
Gladys A. Diebert

Joetta Fleak
Ray G. Seibert



Scott Carter, CE | Gaylord "Rick" Ransom, SE, CE | Arturo Lopez | Nathan Miller, SE, CE
Klare Yavasilis, SE, CE | Eric Bain, CE | Dioselino Garcia-Padron, CE

(559) 449-8444 OFFICE
(559) 449-8404 FAX
info@brooksransom.com EMAIL
brooksransom.com WEBSITE

7415 N. Palm Ave., Ste. 100
Fresno, CA 93711

Addendum No. 1

Date: July 15, 2024

**Football Scoreboard
Madera South High School**

DSA Application Number: 02-122411

**Madera Unified School District
Madera, CA**

BRA Project No. 23313



NOTICE TO ALL CONTRACTORS SUBMITTING BIDS FOR THIS WORK AND TO ALL PLAN HOLDERS:

You are hereby notified of the following changes, clarifications or modifications to the original Contract Documents, Project Manual, Drawings, Specifications, and subsequent Addenda. This Addendum shall supersede the original Contract Documents and previous Addenda wherein it contradicts the same and shall take precedence over anything to the contrary therein. All other conditions remain unchanged.

INDEX OF ADDENDA TRANSMITTED HERewith

ADI-1:

Sheet SB0.2: In structural steel and welding notes:

1. In note 15 delete following in note "or painted with zinc rich primer, undercoat, and finish coat; or equivalent paint system". Steel shall be hot dipped galvanized.

ADI-2:

Sheet SB3.2: In three column scoreboard installation detail:


1. This project will have no flags on top of steel columns.

ADI-3:

Sheet E-2: In Key Notes, revise note to:

14. "Provide 2" C from new scoreboard to existing L.V. pull box for scoreboard control. Contractor to supply new RG58/U cable with terminations per

STRUCTURAL ENGINEERS ASSOCIATION
AMERICAN COUNCIL OF ENGINEERING COMPANIES
AMERICAN SOCIETY OF CIVIL ENGINEERS
EARTHQUAKE ENGINEERING RESEARCH INSTITUTE
INTERNATIONAL CODE COUNCIL



manufacturer's specifications from the new scoreboard to press box with sufficient length to reach termination point inside of scoreboard and controller in press box plus 6' of service loop at each end. Service loop may be installed in closest pull box.”.