

Madera Unified School District

1902 Howard Road, Madera, CA 93637
559.675.4500
Fax: 559.675.1186
www.madera.k12.ca.us

October 22, 2025

Addendum No. 2 -Bid No.100125-MHS Varsity Baseball Irrigation Project

NOTICE TO ALL VENDORS:

This addendum is attached to and made a part of the above-entitled specifications for Madera Unified School District for Bid No.030524-100125-MHS Varsity Baseball Irrigation Project, with a Bid Turn in date of October 21, **28 2025 @ 4:00:00 am-2:00 pm**

All changes and/or clarifications will appear in bold type and deletions will be struck out within a sentence.

Clarifications/Questions

1. **The concrete slabs for the 1st & 3rd base coaches' boxes and the concrete slab for the halo around home plate will need to be formed and new concrete will need to be installed in these areas. (See attached photo)**
2. Will the synthetic grass for the HALO scope be owner furnished, and contractor installed, and the concrete base is to be contractor furnished and contractor installed? **The contractor needs to supply and install concrete. Synthetic grass needs to be supplied by the contractor.**
3. Will the irrigation in the outfield be abandoned in place and replaced with new pipe, sprinklers, and valves? **Irrigation is to be abandoned in place and replaced with new pipe, sprinklers, and valves.**
4. Reference to Bid_No100125-Madera_H.S._Varsity_Baseball_Irrigation_Project-Updated, document 00800 - Special Conditions indicates liquidated damages to be \$500. However, document 00500 - Contract shows \$1,000 per calendar day. Please clarify. **Liquidated Damages will be \$500.00**
5. What is the planned start/end date for this project? **The start date will be June 8, 2026 with and end date of no later than August 3, 2026**
6. Does this project require Skilled and Trained Workforce, PSA/PLA/CWA? **Yes, it requires skilled labor. No PLA. Must be registered with the DIR.**
7. Please clarify whether spoils are to be stockpiled on-site or hauled off-site. **Only infield dirt can be left on site.**
8. Please provide maintenance period for this project. **Three months**


Todd Lile
Superintendent

Board of Trustees
Ray G. Siebert, President

Ruben Mendoza, Clerk
Nadeem Ahmad

Israel Cortes
Gladys A. Diebert

Joetta Fleak
Lucy Salazar



Madera Unified School District

1902 Howard Road, Madera, CA 93637
559.675.4500
Fax: 559.675.1186
www.madera.k12.ca.us

9. Please provide the materials and details for infield material, pitcher's mound, and batter's box. **Refer to the scope of work Miscellaneous section.**
10. Please provide model and detail for controller, control switch, booster switch. **Refer to the scope of work in the Controller section. See attached sports field bypass switch attachment(Switch.jpg,S1GT Coaches Switch.pdf, Switch Diagram PDF See attached**
11. Please provide model and detail for backflow preventor. **Using existing RP**
12. Please provide model and detail for remote control valves. **Hunter Valves**
13. Please provide model for sprinkler heads. **Hunter Sprinklers**
14. Please provide material for mainline pipes. **PVC Scheduled 40**
15. Please provide material for lateral line pipes. **PVC Scheduled 40**
16. Please confirm what the 4" RP is, as called out on 'New Irrigation Valves Location for Infield and Outfield' file. **This is the current location for the RP**
17. Please confirm the excavated soil can be used for backfilling of pipes and sleeves trenching. **Refer to scope of work section Pipe Depth and Backfill. "Backfill for first 6 inches underneath, and 4 inches around and above main line pipe and control wires shall be granular bedding material".**
18. Please confirm whether the irrigation is reclaimed or domestic system? **Domestic**
19. Refer to MHS varsity Baseball Infield 2025 Map, there is a callout for coupler adjacent to the pitcher mound with no main line connection. Please clarify. **1" Quick Coupler Valve**
20. Please confirm that all sod areas (excluding the sod at the infield square, the collar, and 15 feet into the outfield) shall remain in place and will not be replaced with new sod. **Correct, but the field will need to be seeded.**
21. Refer to the scope of work item #3.g, please be more specific about the material and installation for mix of sand, organics, Bermuda seed, and fertilizer. **Refer to the scope of work Miscellaneous section**
22. Please provide application ratio for soil preparation amendment for bidding purpose since the soil analysis has not been conducted at the time of bid. **Refer to the scope of work Miscellaneous section. Existing soil can be used or topsoil**
23. The elevation between the home plate and outfield is approximate 2' depth per job site. Is there any imported topsoil required? If yes, please clearly indicate the area and provide the specification of imported topsoil. **Yes, imported topsoil will be necessary. The contractor will need to determine grades.**


Todd Lile
Superintendent

Board of Trustees
Ray G. Siebert, President

Ruben Mendoza, Clerk
Nadeem Ahmad

Israel Cortes
Gladys A. Diebert

Joetta Fleak
Lucy Salazar



Madera Unified School District

1902 Howard Road, Madera, CA 93637
559.675.4500
Fax: 559.675.1186
www.madera.k12.ca.us

24. The EE is expected to exceed \$150K due to the scope of work, which includes grading and removal. Please advise. **Correct, that is the estimated cost of the project**
25. Please clarify what is the green area as shown in 'Halo image-for concrete' **Turf is installed on top of the concrete.**
26. Please specify the areas where concrete is to be installed per requirement on Scope of work item #4. **Halo, On-deck circles, coach's and thrust blocks**
27. To clarify, the on-deck circles and coach's boxes will NOT be replaced with concrete and synthetic as they are now. **Yes, on-deck circles and coach's boxes to be removed and replaced**
28. Can you please provide the construction drawings/plans which include the current concrete and drainage specs? **Please see the attached topograph map from previous project (02-115348 C3.tif) 1st attached document.**

Signature: _____

Date: _____

Todd Lile
Superintendent

Board of Trustees
Ray G. Siebert, President

Ruben Mendoza, Clerk
Nadeem Ahmad

Israel Cortes
Gladys A. Diebert

Joetta Fleak
Lucy Salazar