

SCOPE OF WORK:

- All work must be performed on weekday, weekends, non-student days, and district holidays or after school hours when students are not present
- Project start date must be coordinated with district to allow over site from district chosen inspector.
- The Contractor will be expected to adjust their work schedule to accommodate the district's needs. The District will not be responsible for paying overtime.
- The Contractor will provide their own storage (lockable container, etc.) for all necessary equipment and materials...
- Contractor is responsible to remove and haul away of existing flooring and base
- Install entry mat system-entry mat size minimum of 4'x4'
- Pull and replace thresholds
- Furnish 4" rubber base-Burke coved base: True Blue or equal
- Prep floor surfaces
- Materials will be shipped to school sites
- Moisture mitigation-any issues will be handled by District
- Sub-floor repairs-If any issue arises please notify District immediately

Carpet: Patcraft Big Splash EcoWorx Performance Broadloom, Tarkett Infinity 0589, or equal.
Wal-off mat Patcraft Paseo Modular or equal.

Rooms to get carpet:

Desmond Elementary: 201-208, 602, 603, 1801, Library, Office (all)
Eastin-Arcola: 1-10, 13-23, Office (all)
La Vina: Workroom
Pershing: 301-309, 401-410, 501-512, Library, Lounge, Office (all)
Sierra Vista: Lab 2
Washington: 10, 25

SPECIAL CONDITIONS:

1. Close Out Documentation: must provide the District with Warranties, Maintenance Instructions and any pertinent guidelines
2. Time of Completion: The District has determined time of completion to be no later than August 06, 2021.
3. Estimated Schedule of Work: Notice to Proceed Date: June 1, 2021
Hours of Work: 6:00 A.M to 5:00 P.M.
4. Low bid determination: Low bid will be determined by total of Base bid. and all completed forms/samples and Job – Walk attendance.