

Selective Demolition

Scope of Work

Madera South High School

- a. Remove 4 ice storage tanks, associated piping, pipe trees or stands, anchors
- b. Remove 2 circulation pumps, associated piping, pipe or pump supports/stands
- c. Remove 2 electrical service disconnects and 2 electrical control panels.
- d. Remove 1 heat exchanger, associated electrical conduit and concrete equipment pad (South side of McQuay Chiller).
- e. Remove 1 heat exchanger, associated electrical conduit and concrete equipment pad, all tagged piping and piping supports (North side of McQuay Chiller).
- f. Remove Propylene Glycol inside the ice storage tanks (approx. 3200 gallons). Disposal of the glycol per EPA requirements and the State of California.

Eastin-Arcola

- a. Remove 1 boiler
- b. Remove related gas and water piping to the shut off valves.
- c. Remove all boiler exhaust duct. Leave roof jack and cap.
- d. Remove 1 each water storage tank and related water piping
- e. Remove all boiler electrical conduit and wiring.