

Tile Installation-Scope of Work

Location of Work

Madera High School

- A. Building 200
 - a. 1 ea. Boys restroom, 1 ea. Girls restroom, 1 ea. Staff Men's room, 1 ea. Staff Women's restroom, 2 ea. hallway water fountain cut out
- B. Building 300
 - a. 1 ea. Staff restroom in the media room
- C. Building 600
 - a. 1 ea. Boys restroom, 1 ea. Girls restroom
- D. Building 700
 - a. 1 ea. Staff restroom in room 702
- E. Building 800
 - a. 1 ea. Boys restroom, 1 ea. Girls restroom, 1 ea. Men's Staff restroom, 1 ea. Women's Staff restroom, 1 ea. hallway water fountain cut out
- F. Drama Theatre
 - a. 1 ea. Boys restroom, 1 ea. Girls restroom
- G. Flores Gym
 - a. 1 ea. Boys restroom, North shower area, South shower area, Wrestling room Coaches office restroom

Stadium Fieldhouse on Coyote Lane

- A. Boys restroom and Shower area

Eastin-Arcola Elementary School

- A. 4 ea. Boys restrooms, 4 ea. Girls restrooms. Restrooms are located on the exterior ends of the classroom wings.

Work to be Performed

- A. Removal and disposal of all plumbing fixtures and partitions. Removal and disposal of existing tile and wall components to expose bare wood studs. Existing floor tile to remain, new floor tile to be installed over existing floor tile. Secure and protect existing plumbing water and drain connections.
- B. Reinstall 1/2" USG Durock brand cement board over 19/32" Oriented Strand Board (OSB) where existing tile and wallboard was removed. Install new wall and floor tile. Height of the new wall tile will be the same as the removed tile. See reference pictures for color and pattern.

District Self-Performed Work – Contractor Coordination

- A. The District may need to lower water and drain connections of some urinals to be compliant with ADA requirements. In building 200 at Madera High School 5 floor mount urinals will need to have the drain pipe relocated to the wall. The contractor will coordinate with the District and allow 5 days for the District to complete this work.
- B. The District will install all new water closet carriers and urinal backing plates. The contractor will coordinate with the District and allow time for the District to complete this work prior to install of OSB/Durock/tile.
- C. The District will provide and install all new plumbing fixtures, partitions and accessories.